6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for the construction of a Town Hall at Challakere.

Serial No.	Details of work	Per	Quantity
1	Earthwork excavation for foundation	C.yd.	133
2	Concrete foundation (stone jelly in mortar)	C.ft.	1316
3	Size stone in mortar filling in foundation	,,	3769
4	Superstructure :—Burnt brick in mortar	,,	4968
5	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	619
6	Mortar plastering	Sqr.	84·62
7	White washing	,,	84·62
8	Rolled steel girders including hoisting and fixing with painting...	Cwt.	110·89
9	Pukka terrace roofing 9″ thcik, complete	Sqr.	15·48
10	Cornice work	R.ft.	286
11	Parapet wall 9″ thick over terrace complete	,,	264
12	Teakwood doors with $3\frac{1}{2}''\times5''$ frames $1\frac{1}{2}''$ glazed shutters in 3 portions with $1\frac{1}{2}''$ panneled including clamps, hinges, bolts, handles, lock, etc., complete.	S.ft.	209
13	Windows with teak frames of $3''\times5''$ with $1\frac{1}{2}''$ thick shutters in 3 portions in two halves inside with bottom panneled and top glazed including fittings, etc., complete.	,,	36
14	Teakwood windows with $3\frac{1}{2}''\times4\frac{1}{2}''$ frame $1\frac{1}{4}''$ thick shutters in four halves inside glazed outside panneled with $\frac{3}{4}''$ dia. iron bars including fitting completed.	,,	192
15	Renco Honey comb ventilators	,,	48
16	Parapet wall 9″ thick brick in mortar Cadappa slab coping over cornice including plastering in verandah.	R.ft.	32
17	Stucco work for forming base and capital for pillasters and pillars alround the building.	Lump	sum
18	Mouldings by the side of windows and openings with ornamental works--18 in number.	Lump	sum
19	Flooring with Cudappa slab $1\frac{1}{2}''$ to 2″ thick over 3″ concrete and cement pointing.	Sqr.	5·72
20	Flooring with 1st Class Mangalore tiles on 3″ concrete bed and cement pointing.	,,	11·40
21	Silicate painting to doors and windows...	,,	10·64
22	Cement pointing to basement	,,	6·36
23	Making holes in the cill slab of doors to receive door frames ...	Each	14
24	Brick in mortar binding wall over terrace including plastering ...	R.ft.	46
25	Providing zinc down water pipes of 3″ to 4″ diameter ...	,,	196
26	Providing slabs to the down water pipes where water falls at ground level.	Each	12
27	Sundry unforeseen works such as clearing site and hardening ground, drainage, etc, complete.	Lump	sum

A. TANDONI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE ENTOMOLOGIST, DEPARTMENT OF AGRICULTURE IN MYSORE, BANGALORE.

TENDER FOR THE SUPPLY OF FURNITURE.

Notification dated 29th January 1929.

Notice is hereby given that sealed tenders will be received at the office of the Entomologist, Department of Agriculture in Mysore, Bangalore, during office hours upto 23rd February 1929, from approved contractors who are willing to undertake the supply of teakwood furniture as noted below.

For further particulars please see page 176, Part VI of the *Mysore Gazette* of 7th February 1929.

B. C. SHANTAPPA,
For *Entomologist.*